



REV	DESCRIPTION	BY	DATE
4	UPDATE TO MARK UP DEC 10 2018	E SMITH	12-11-18
3	UPDATE TO MARK UP NOV. 29	TEC	12-04-18
2	UPDATE TO CHANGE ORDER "X"	E SMITH	11-09-18
1	ADD GENERATOR & PORTABLE PUMP	JOL	13-08-18
A	CHANGED CAB TO 4DOOR PER RFD H REQUEST JULY 11/18	TEC	07-12-18
0	FIRST ISSUE		
	DESCRIPTION	BY	DATE

CHASSIS: FREIGHTLINER M2 106 4 DOOR
 PUMP: WATEROUS CXVA 1050 IGPM PTO DRIVE
 TANK: 1000 Imp. Gal POLYPROPYLENE
 1-30 Imp. Gal FOAM CELL
 FOAM: FOAMPRO 1600

SUCTION: 1 - 6" LEFT (NO GATE)
 1 - 6" RIGHT (NO GATE)
 1 - 3" TANK TO PUMP (4" PIPING)
 1 - 2 1/2" LEFT
 1 - 2 1/2" RIGHT

DISCHARGES: 2 - 2 1/2" LEFT
 2 - 2 1/2" RIGHT
 2 - 2 1/2" REAR
 2 - 1 1/2" SPEEDLAYS (FOAM)
 1 - 1 1/2" FRONT TRASHLINE (FOAM)
 1 - 2" TANK FILL

WASAUKSING FIRST NATION
 FIRE DEPARTMENT
 JOB NO. 20292
 DRAWN BY E SMITH
 DATE 03-16-2018
 METALFAB LTD.
 847 CENTRAL ST. CENTREVILLE
 NB. CANADA E7K 2E8

TITLE: GENERAL ARRANGEMENT

DRAWING NO. FT-11050
 REV 4

ALL DIMENSIONS ARE IN INCHES AND APPROXIMATE